Summary Schedule		
Bar Diameter	Total Bar Length	Weight
8 mm	408975 mm	161.58 kg
10 mm	24750 mm	15.28 kg
12 mm	20925 mm	18.60 kg
16 mm	65500 mm	103.51 kg
20 mm	25675 mm	63.40 kg
25 mm	5200 mm	20.06 kg
	551025 mm	382.44 kg

Rebar schedule for PW-GF-08(A)








Schedule Mark	Bar Diameter	Shape	A	B	C	D	E	G	Bar Length	Total Bar Length	Quantity	Weight
A	8 mm	M_00	0 mm	2015 mm	0 mm	0 mm	0 mm	0 mm	2025 mm	60750 mm	30	24.00 kg
A1	8 mm	M_00	0 mm	2095 mm	0 mm	0 mm	0 mm	0 mm	2100 mm	63000 mm	30	24.89 kg
A2	8 mm	M_00	0 mm	4995 mm	0 mm	0 mm	0 mm	0 mm	5000 mm	60000 mm	12	23.71 kg
A3	8 mm	M_00	0 mm	5035 mm	0 mm	0 mm	0 mm	0 mm	5050 mm	55550 mm	11	21.95 kg
B	8 mm	M_17	0 mm	400 mm	90 mm	400 mm	0 mm	0 mm	875 mm	45500 mm	52	17.98 kg
B1	8 mm	M_17	0 mm	400 mm	120 mm	400 mm	0 mm	0 mm	900 mm	19800 mm	22	7.82 kg
B2	8 mm	M_17	0 mm	400 mm	140 mm	400 mm	0 mm	0 mm	900 mm	53100 mm	59	20.98 kg
C	8 mm	M_17A	0 mm	645 mm	580 mm	0 mm	0 mm	0 mm	1225 mm	13475 mm	11	5.32 kg
D	8 mm	M_T1	70 mm	330 mm	220 mm	330 mm	220 mm	70 mm	1200 mm	28800 mm	24	11.38 kg
E	8 mm	M_T10	70 mm	220 mm	0 mm	0 mm	0 mm	70 mm	375 mm	9000 mm	24	3.56 kg
F	12 mm	M_00	0 mm	1960 mm	0 mm	0 mm	0 mm	0 mm	1975 mm	1975 mm	1	1.76 kg
F1	12 mm	M_00	0 mm	2095 mm	0 mm	0 mm	0 mm	0 mm	2100 mm	6300 mm	3	5.60 kg
G	12 mm	M_T1	105 mm	250 mm	250 mm	250 mm	250 mm	105 mm	1150 mm	12650 mm	11	11.25 kg
H	16 mm	M_00	0 mm	2365 mm	0 mm	0 mm	0 mm	0 mm	2375 mm	14250 mm	6	22.52 kg
H1	16 mm	M_00	0 mm	4995 mm	0 mm	0 mm	0 mm	0 mm	5000 mm	20000 mm	4	31.61 kg
I	16 mm	M_17	0 mm	800 mm	200 mm	800 mm	0 mm	0 mm	1750 mm	5250 mm	3	8.30 kg
I1	16 mm	M_17	0 mm	800 mm	310 mm	800 mm	0 mm	0 mm	1850 mm	3700 mm	2	5.85 kg
I2	16 mm	M_17	0 mm	800 mm	1995 mm	800 mm	0 mm	0 mm	3525 mm	14100 mm	4	22.28 kg
J	16 mm	M_17A	0 mm	1275 mm	800 mm	0 mm	0 mm	0 mm	2050 mm	8200 mm	4	12.96 kg
K	20 mm	M_00	0 mm	2020 mm	0 mm	0 mm	0 mm	0 mm	2025 mm	6075 mm	3	15.00 kg
L	20 mm	M_17	0 mm	445 mm	620 mm	445 mm	0 mm	0 mm	1425 mm	2850 mm	2	7.04 kg
L1	20 mm	M_17	0 mm	230 mm	1330 mm	800 mm	0 mm	0 mm	2275 mm	4550 mm	2	11.24 kg
M	25 mm	M_17	0 mm	230 mm	1330 mm	1125 mm	0 mm	0 mm	2600 mm	5200 mm	2	20.06 kg
										514075 mm	322	337.03 kg

Rebar schedule for PW-GF-08(B)

Schedule Mark	Bar Diameter	Shape	A	B	C	Bar Length	Total Bar Length	Quantity	Weight
N	20 mm	26	1145 mm	290 mm	4650 mm	6100 mm	6100 mm	1	15.06 kg
N1	20 mm	26	1145 mm	300 mm	4640 mm	6100 mm	6100 mm	1	15.06 kg
							12200 mm	2	30.13 kg

Rebar schedule for PW-GF-08(C

Schedule Mark	Bar Diameter	Shape	A	B	C	D	E	Bar Length	Total Bar Length	Quantity	Weight
O	10 mm	Rebar Shape 9	740 mm	315 mm	200 mm	335 mm	745 mm	2250 mm	24750 mm	11	15.28 kg
									24750 mm	11	15.28 kg

Rebar Shape	Shape Image
M_00	
M_17	
Rebar Shape 9	
M_17A	
26	
M_T1	
M_T10	

PROJECT -:
MF FACTORY

GENERAL NOTES:

GRADE OF CONCRETE - M40
GRADE OF STEEL - Fe500
STRIPPING STRENGTH - M20

COVER

WALL - 30mm
CORBEL - 25mm

ALL DIMENSIONS ARE IN MM

LEGENDS:

ERECTION MARK -
MOULD FACE - MF

CONTRACTOR -:

VME Precast Products

Arihant Esta, 2g2, 2nd floor,
No.370, Church Road, Mogappair East,
Chennai-600037.
Tel:+91- 98400 - 41400 / 90802 - 22066

STRUCTURAL CONSULTANT -:

ES STRUCTURAL CONSULTANT
B167, 12th cross street, Jawahar Nagar,
Palayamkottai, Tirunelveli-627007
Cell No: +91 9865803764

Rev	Date	Description	Chkd	Appd.
0	14-06-25	FOR APPROVAL	PK	PRC

REVISION SCHEDULE

DRAWING TITLE -:

PW-GF-08-BBS

JOB NO. : ESP24075	DRAWN BY:- IH
ELEMENT NO. : PW-GF-08	SHEET SIZE:- A3
DWG. NO. : PW-GF-08(S)	REV.NO:- 0
SCALE :	LEVEL. :